

**ADDENDUM NO. 2
TO
CCTV AND SONAR INSPECTION OF PIPES PENETRATING THE LEVEE IN
THE GARY NORTH, GARY SOUTH AND INDOT SEGMENTS
LITTLE CALUMET RIVER BASIN DEVELOPMENT COMMISSION**

RESPONSES TO CONTRACTOR QUESTIONS

1. The pay item for the 96" Pipeline Cleaning has a unit of CYS instead of LFT like all the other cleaning pay items. Is this the anticipated volume of debris? Can you please confirm this is correct?

Change the pay item for 96" Pipeline cleaning to LFT with a quantity of 2,960.
2. The televising pay items for the 96" is 3,256'. I am only seeing 2,960' on the plans. Please confirm this pay item is only for the 4 culverts crossing I-80/94 and 4 culverts crossing Georgia Street.

Change the quantity of pay item for 96" Televising to 2,960 LFT for the 4 culverts crossing I-80/94 and the 4 culverts crossing Georgia.
3. Will the contractor be given an area to store roll off boxes for debris storage and equipment?

No equipment can be stored on the levees overnight. Equipment stored on site shall be barricaded with the appropriate form of traffic maintenance. Access to the top of levee shall be maintained throughout the length of the project in the event of maintenance or flood control action is required. Site shall be inspected and cleaned of loose debris, trash, and construction material daily – especially on the levees and pedestrian pathways. Project debris shall be continuously removed and not stored on-site per Special Provision Section 311000 "Site Clearing".
4. Does there need to be a separate bid bond for each area or the total project including all three areas?

A separate bond for each project.
5. I do not see Sonar mentioned anywhere in the spec other than the title of the project. Is Sonar required for this project?

The word "Sonar" should be ignored. Refer to Special Provision Section 330130 "Operation and Maintenance of Utilities" for televising activities.